

Data Center Architecture



Data Center Requirements



Requirements

- Provide a physical secure location for servers, storage, and network equipment.
- Provide 24x7 network connectivity for equipment within the datacenter to devices outside the data center
- Provide necessary power to operate all equipment
- Provide an environment where the temperature and humidity are controlled within a narrow range and air exchanged at an adequate rate.



Required Physical Area for Equipment and Unoccupied Space

- servers
- storage
- network devices
- HAVAC (heating ventilation and air conditioning)
- power panels
- breakers
- floor to support the height of the equipment



Required Physical Area for Equipment and Unoccupied Space

- Components stored in racks.
- Height of equipment measured in U's; $1U=1,75''$.
- 50% of space occupied by racks and stand alone hardware.
- 50% of space for aisles, ramp, space next to walls, breaks between rows of racks and open space to let exhaust air from racks to the HVAC.
- Plan for the growth



Required Power to Run All the Devices

- UPS must be present to protect against power failures.
- Generators may be required if outages are frequent and take long.
- Start by collecting the power requirements of the equipment.
- This will define the number of
 - breakers
 - outlet types, single-phased or three-phased,
 - layout of data wiring
- Plan for the growth



Required Cooling and HVAC

- Keep devices cool
- Maintain low humidity within the data center
- Measured in British Thermal Units (BTUs) per hour
- Collect the BTUs requirements of all equipment to establish the HVAC necessities
- Plan for the growth



Required Weight

- Determine the weight of all empty racks
- Determine the weight of all equipment
- Determine if the existing data center floor is strong enough for the weight



Required Weight

- Types of load that the floor must support
 - Maximum weight that the entire data-center floor can support
 - Maximum weight that a single tile can support
 - Maximum point load that a tile can support



Required Network Bandwidth

- The bandwidth offered by the ISP should at least be equal to the data center's inbound and outbound bandwidth specifications
- If business-critical servers must be connected to the internet, reliable and redundant ISP links are mandatory
- Most of the wiring requirements can be fulfilled with
 - Cat6 copper
 - multi-mode fiber
 - single mode fibers may be needed for WAN connections, NAS, network-I/O bound servers



Selecting a Geographic Location

- Safe from natural hazards
 - floods, fire, tornados, strong winds, earthquakes
- Safe from man-made disasters
 - Should not be close to an airport, electrical railways or telecommunications signal center because of RFI and EMI
 - Should not be close to a mine, quarry, highway or heavy industrial plant
 - Should be away of sources of pollution
- Availability of local technical talent
- Abundant and inexpensive utilities such as power and water



Selecting an Existing Building (Retrofitting)

- There must be enough space for a raised floor
- If network and electrical cables will be run in the subfloor plenum, they must not obstruct the flow of cold air
- It must be easy to setup T1, DS3, fiber-optic, and other high bandwidth network links
- The building must have adequate power and redundant electrical grids to guarantee 24x7 operations
- The room or floor must be large enough for present and future equipment
- The data center must be isolated from contaminant-producing areas within the building



Selecting an Existing Building (Retrofitting)

- The exhaust from generators and other sources should not be allowed to enter the data center air intakes
- The gas and water pipes must be safe and leak-free.



Remarks

- The functional requirement of a data center is to provide a safe and secure place for servers, storage, and networking equipment.
- The data center must also provide the required power, a well-controlled environment (with regard to temperature and relative humidity), and network connectivity to other devices within and outside the data center.



Guides for Planning a Data Center

- Plan in advance
- Plan for the worst
- Plan for growth
- Simplify your design
- Plan for changes
- Label all equipment, especially cables and ports



Characteristics of an Outstanding Design

- Design must be simple
 - all cables, circuit breakers, servers, storage devices, networks ports and power outlets must be labeled
- Design must be scalable
- Design must be modular
- Design must be flexible



Data Center Structures

- No-Raised or raised floor
- Aisles
- Ramp
- Compulsory local building codes



Raised Floor Design and Deployment

- place for the equipment to sit
- grounding for the equipment
- a means to channel cold air from the HVAC
- place to route network cables, power outlets and cables for the equipment on the tiles



Raised Floor Design and Deployment

- Plenum

space between the datacenter subfloor and the floor tiles. The HVAC must be capable of pressurizing it

- Floor tiles

floor panels that provide a supporting base for the racks and equipment.

Can be solid or perforated

- Equipment Weight and Tile Strength

Point load

Static Load

- Electrical wireways

- Cable trays



Design and Plan Against Vandalism

- For most organizations, online data is one of their most expensive assets
- Data center must be selected in a building or neighborhood where it is easy to control access
- The data center must not be accessible from the outside
- Should have various monitoring devices, motion sensors and alarms
- Unauthorized accesses to the data center should be prevented



Best Practices

- The design must be modular
- Label everything
- Document everything
- Isolate cables
- Use cast aluminium tiles



Remarks

- It is important to get the design right because retrofitting a data center is too expensive and unwieldy.
- A data center design must be simple to modify and manage, scalable to accommodate future needs without any changes, and modular and flexible so upgrades can be made if necessary.
- Common structures within a data center are raised floor, aisles, floor tiles, subfloor plenum and ceiling plenum, electrical wireways, and cable trays.
- All equipment, cable ends, and grid locations must be labeled in an orderly manner.



Modular Cabling Design

- Keep it simple
- Patch panels



Points of Distribution (PODs)

- Rack with devices
- network switches
- terminal servers
- patch panels



Best Practices

- Label your equipment
- Color code cables
- Avoid a tangle of cables
- Patch panel ports and connections must be verified by the installer
- Remote console access
- cable bending radius



Remarks

- The network and cabling infrastructure within a data center must be modular, which is possible using patch panels and points of distribution containing cross-patch ports, network subswitches, and terminal servers.
- All cable connections must be well labeled.
- Internet access from ISPs must be redundant and reliable.



Data Center Maintenance



Network Operations Center (NOC)

- Dedicated facility staffed with people who monitor the availability of all devices and services within the data center and respond to any data center problems.
- Central logging point for all alarms and for evaluating the present status of the data center



Network Monitoring

- Gathering real-time data and its classification into performance and outages
- Used to predict the need for future scaling
- Outage info is used to alert staff and early problem resolution
- SNMP
- In-band and out-of-band monitoring



Data Center Physical Security

- All entry points and doors must be controlled by card readers or persons who monitor and restrict access to those entering the data center.
- Co-location DC
- Managed hosting DC
- CCTV



Data Center Cleaning

- Do not require regular cleaning or vacuum.
- Approved cleaning supplies.

HEPA vacuums, three pin ground configured outlets, antistatic materials.

- Floor surface cleaning.
avoid disturbing cables

- Subfloor and above-ceiling plenum cleaning
the space above the tiles must be cleaned. Care must be taken when removing the tiles

- Equipment cleaning

Chemicals must not be used directly on equipment



Best Practices


- A high level of physical, network, and host level security must be enforced at all times.
- Regular cleaning of the data center is important to remove all dust and dirt, which can damage devices.
- Quarterly, preventive maintenance must include
 - UPS and batteries
 - Generator and automatic transfer switch (ATS)
 - Power cables, outlets, subpanels and circuit breakers
 - static switching equipment



Best Practices

- Free-standing and rack based power distribution equipment.
- Fire suppression and detection equipment.
- Overhead sprinkler systems.
- Air conditioning and HVAC units, air ducts, and filters
- Inlet-air blockages near perforated tiles
- Physical site inspection every month.
- A copy of all documents and standard operating procedures must be maintained at a central web site.











Power Distribution



Estimating Your Power Needs

- Power for racks and stand-alone equipment
- Power for the HVAC System

A majority of the equipment power should be allocated for the HVAC

- Power for lighting, monitoring systems, NOC servers, fire control devices,...



- Uninterruptible Power Supply (UPS)
- Generators
- Power Conditioning
- Single phased and three phase power
- Power distribution units (PDUs)
- Electrostatic Discharge (ESD)



Data Center HVAC



HVAC

- Must be redundant to cope with failures and maintenance
- Must be efficient. Account for 40 to 60% of the power used in the DataCenter

Environmental factor	Temperature	Relative Humidity
Optimal range	21°C to 23°C	45-50%
Acceptable Range	10°C to 32°C	25-75%



Narrow Range in temperature and RH

- Servers and storage generate substantial amounts of heat
- Certain areas require more cooling
- The weather is unpredictable
- Equipment changes within the data center
- Numerous air exchanges
- High RH causes corrosion and short circuits
- Low RH causes ESD problems
- Data center activities that can disrupt the temperature profile



Air conditioning Systems

- Cold-Liquid Air-Conditioning
 - for hot, desert regions
- Dry Air-Conditioning
 - for humid regions
- Air Circulation
 - Airflow pattern with subfloor supply and overhead return vents
 - Airflow pattern with overhead supply and return vents



Air Placement of Hardware Racks

- Bottom-to-Top Cooled Racks
- Top-to Bottom Cooled Racks
- Front-to-Front Cooled Racks
- Front-to-Back Cooled Racks



Best Practices

- Should exist cold and hot aisles. Racks should be set back-to-back pointing to the hot aisle and front-to-front facing the cold aisle
- Devices are designed to expel their own heat in an optimal manner. The air-flow pattern must pick-up hot air and transport it to the HVAC
- Different perforation levels for tiles in the cold aisle balance air-flow patterns. Hot aisles should not contain perforated tiles
- Devices with lower temperature requirements must be placed on the lower half of the racks, and high heat-generating devices in the upper half



Best Practices

- Incoming air-flow rates must be balanced to maintain a uniform temperature along the rack height
- Since cables impede air flow, they must be bundled properly and correct sized cables must be used to keep air-flow passages as open as possible



Key points

- The heat loads within each data center continue to rise at a fast rate
- The objective of the HVAC is to provide enough cold air flow to maintain a temperature that meets the equipment requirements
- Cold-liquid and dry air conditioning systems are commonly used for DC cooling
- Data centers are arranged into cold and hot aisles



Data Center Classification



	Tier I	Tier II	Tier III	Tier IV
Number of power delivery paths	Only 1	Only 1	1 Active 1 Passive	2 Active
Redundancy	N	N+1	N+1	S+S or 2(N+1)
Compartmentalization	No	No	No	Yes
Concurrently Maintainable	No	No	Yes	Yes
Fault tolerance to Worst Event	None	None	None	Yes

